

## WOLF & JORDAN RIVERS, MISSISSIPPI

### CONDITION OF IMPROVEMENT ON 30 SEPTEMBER 1989

*Existing Project:* The existing project provides for 7 foot by 100 foot channels from the 7 foot contour in St. Louis Bay to the 7 foot contour in each stream. Channel lengths are 1.6 miles for Wolf and 2 miles for Jordan River.

This portion of the project was authorized by the R. & H. Act of 2 March 1907 (H. Doc. 917, 59th Cong., 1st sess.). The Water Resources Development Act of 28 April 1988 (S. 2100, 100th Cong., 2nd sess.) further authorized assumption of maintenance of the Bayou Portage Segment to 8 feet deep, 100 feet wide, and 4 1/2 miles long.

*Progress:* Wolf and Jordan River Channels completed in 1908. Bayou Portage portion of the project has not yet been funded.

*Cost of Construction:* \$29,195.

*Tidal Range:* Mean, 1.6 feet; Extreme, 3.3 feet.

*Controlling Depth:* Wolf River, 7.0 feet; Jordan River, 7.0 feet.

*Local Sponsor:* None.